

SECTION 32 14 13.16
(Section 02784)
PAVING SLABS

Prado

ON AN AGGREGATE BASE

NOTE: This guide specification for the U.S. is for paving slabs on a sand bed over a compacted aggregate base for residential pedestrian and golf cart applications. Excavation and preparation of soil subgrade, subgrade drainage and the aggregate base are by others. Units no larger than 14 in. x 14 in. (350 mm x 350 mm) paving slabs are recommended for these applications. Slabs installed with these methods are not recommended for commercial or municipal applications, or areas subject to vehicular traffic. The text must be edited to suit specific project requirements for projects. This Section includes the term "Architect." Edit this term as necessary to identify the design professional in the General Conditions of the Contract.

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes:
1. Paving slabs
 2. Bedding and joint sand.
 3. Edge restraints.
 4. [Geotextile].
 5. [Cleaning, Sealing, and Joint sand stabilization].
- B. Related work
1. Section [] – Earthwork.
 2. Section [] – Grading.
 3. Section [] – Aggregate base.
 4. Section [] - Concrete [Walks] [Curbs] [and] [Gutters].

1.02 REFERENCES

American Society for Testing and Materials (ASTM):

1. ASTM C 33, Standard Specification for Concrete Aggregates.
2. ASTM C 136, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
3. ASTM C 140, Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units.
4. ASTM C 144, Standard Specification for Aggregate for Masonry Mortar.
5. ASTM C 936, Standard Specification for Solid Concrete Interlocking Paving Units.
6. ASTM C 979, Standard Specification for Pigments for Integrally Colored Concrete.
7. ASTM D 698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,000 ft-lbf/ft³ (600 kN-m/m³)).
8. ASTM D 1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³)).

Interlocking Concrete Pavement Institute (ICPI)

1. ICPI Tech Spec technical bulletins.

1.03 SUBMITTALS

- A. Shop drawings: Indicate perimeter conditions, relationship to adjoining materials and assemblies, expansion and control joints, paving slab [layout,] [patterns,] [color, arrangement,] installation [and setting] details.
- B. Sieve analysis per ASTM C 136 for the bedding and joint sands.
- C. Paving slabs: Prado

1. [Four] representative full-size samples of each slab type, thickness, color, finish. Select samples to indicate the extremes of color and texture expected in the finished installation.
2. Accepted samples become the standard of acceptance for the work of this Section.
3. Rinox catalog literature and material safety data sheets for the safe handling of the specified materials and products.

1.04 QUALITY ASSURANCE

- A. Paving Subcontractor Qualifications:
 1. Utilize an installer having successfully completed concrete paving slab installation similar in design, material, and extent indicated on this project.
 2. Utilize an installer holding a current certificate from the Interlocking Concrete Pavement Institute Concrete Paver Installer Certification program.
- B. Regulatory Requirements and Approvals: [Specify applicable licensing, bonding or other requirements of regulatory agencies.].
- C. Mock-Ups:
 1. Install a 7 ft x 7 ft (2 x 2 m) slab area.
 2. Use this area to determine surcharge of the bedding layer, joint sizes, lines, laying pattern(s), color(s), and texture of the job.
 3. This area will be used as the standard by which the work will be judged.
 4. Subject to acceptance by owner, mock-up may be retained as part of finished work.
 5. If mock-up is not retained, remove and properly dispose of mock-up.

1.05 DELIVERY, STORAGE & HANDLING

- A. General: Comply with Division 1 Product Requirement Section.
- B. Comply with manufacturer's ordering instructions and lead-time requirements to avoid construction delays.
- C. Delivery: Deliver materials in manufacturer's original, unopened, undamaged containers packaging with identification labels intact.
 1. Coordinate delivery and paving schedule to minimize interference with normal use of buildings adjacent to paving.
 2. Deliver concrete paving slabs to the site in steel banded, plastic banded or plastic wrapped packaging capable of transfer by forklift or clamp lift.
 3. Unload slabs at job site in such a manner that no damage occurs to the product.
- D. Storage and Protection: Store materials protected such that they are kept free from mud, dirt, and other foreign materials. [Store concrete paving slab cleaners and sealers per manufacturer's instructions.]
 1. Cover bedding sand and joint sand with waterproof covering if needed to prevent exposure to rainfall or removal by wind. Secure the covering in place.

1.06 PROJECT/SITE CONDITIONS

- A. Environmental Requirements:
 1. Do not install sand or slabs during heavy rain or snowfall.
 2. Do not install frozen bedding sand.
 3. Do not install concrete slabs on frozen aggregate base or bedding sand.

1.07 MAINTENANCE

- A. Extra Materials: Provide additional material for use by owner for maintenance and repair.
- B. Slabs shall be from the same production run as installed materials.

PART 2 PRODUCTS

2.01 CONCRETE PAVING SLABS

- A. Manufacturer:
[Rinox Pavers LLC](http://www.RinoxPavers.com),
23 Quarry Road
Douglassville, PA 19518
P: 610-323-8800, F: 610-323-6601
www.RinoxPavers.com

B. Concrete paving slabs:

1. Slab type: [Prado](#) Patio System
a. [Prado](#) Interlocking Concrete Paving Slabs:
- | <u>Shape</u> | <u>Thickness</u> | <u>Dimensions</u> |
|--------------|------------------|-------------------|
| Stone - A | 2-3/8" | 4" x 8" |
| Stone - B | 2-3/8" | 8" x 8" |
| Stone - C | 2-3/8" | 8" x 16" |
| Stone - D | 2-3/8" | 16"x 20" |

**All nominal stone sizes are included on one pallet (packaging unit). Irregular stones sizes fit together in a pattern.*

- b. Color:

2.02 PRODUCT SUBSTITUTIONS

- A. Substitutions: No substitutions permitted.

2.03 BEDDING AND JOINT SAND

- A. Provide bedding and joint sand as follows:
1. Clean, non-plastic, free from deleterious or foreign matter, symmetrically shaped, natural or manufactured from crushed rock.
 2. Do not use limestone screenings, stone dust, or sand for the bedding sand material that does not conform to the grading requirements of ASTM C 33.
 3. Do not use mason sand or sand conforming to ASTM C 144 for the bedding sand.
 4. Sieve according to ASTM C 136.
 5. Bedding Sand Material Requirements: Conform to the grading requirements of ASTM C 33 with modifications as shown in Table 1.

Table 1
Grading Requirements for Bedding Sand
ASTM C 33

Sieve Size	Percent Passing
3/8 in.(9.5 mm)	100
No. 4 (4.75 mm)	95 to 100
No. 8 (2.36 mm)	85 to 100
No. 16 (1.18 mm)	50 to 85
No. 30 (0.600 mm)	25 to 60
No. 50 (0.300 mm)	10 to 30
No. 100 (0.150 mm)	2 to 10
No. 200 (0.075 mm)	0 to 1

Note: Coarser sand than that specified in Table 2 below may be used for joint sand including C 33 material as shown in Table 1. Use material where the largest sieve size easily enters the smallest joints. For example, if the smallest slab joints are 2 mm wide, use sand 2 mm and

smaller in particle size. If C 33 sand is used for joint sand, extra effort may be required in sweeping material and compacting the slabs order to completely fill the joints.

6. Joint Sand Material Requirements: Conform to the grading requirements of ASTM C 144 as shown with modifications in Table 2 below:

Sieve Size	ASTM C 144	ASTM C 144
	Natural Sand Percent Passing	Manufactured Sand Percent Passing
No. 4 (4.75 mm)	100	100
No. 8 (2.36 mm)	95 to 100	95 to 100
No. 16 (1.18 mm)	70 to 100	70 to 100
No. 30 (0.600 mm)	40 to 75	40 to 100
No. 50 (0.300 mm)	10 to 35	20 to 40
No. 100 (0.150 mm)	2 to 15	10 to 25
No. 200 (0.075 mm)	0 to 1	0 to 10

Note: Specify specific components of a system, manufactured unit or type of equipment. See ICPI Tech Spec 3, Edge Restraints for Interlocking Concrete Pavements for guidance on selection and design of edge restraints.

2.04 EDGE RESTRAINTS

- A. Provide edge restraints installed around the perimeter of all interlocking concrete paving unit areas as follows:
 1. BEAST plastic edge restraint
 2. Alternative Materials: [Concrete] [Aluminum] [Steel] [Pre-cast concrete] [Cut stone] [Concrete].

PART 3 EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. [Specify acceptable paving subcontractors.].

3.02 EXAMINATION

- A. Acceptance of Site Verification of Conditions:

Note: Compaction of the soil subgrade is recommended to at least 98% standard Proctor density per ASTM D 698 for pedestrian areas and residential driveways. Stabilization of the subgrade and/or base material may be necessary with weak or saturated subgrade soils.

Note: Local aggregate base materials typical to those used for highway flexible pavements are recommended, or those conforming to ASTM D 2940. Compaction of aggregate is recommended to a minimum of 98% Proctor density in accordance with ASTM D 698 is recommended for pedestrian and areas and residential driveways, and a minimum of 98% modified Proctor density in accordance with ASTM C 1557 for all other areas subject to vehicular traffic. Mechanical tampers are recommended for compaction of soil subgrade and aggregate base in areas not accessible to large compaction equipment. Such areas can include that around lamp standards, utility structures, building edges, curbs, tree wells and other protrusions.

Note: Prior to screeding the bedding sand, the recommended base surface tolerance should be $\pm 3/8$ in. (± 10 mm) over a 10 ft. (3 m) straight edge. See ICPI Tech Spec 2, Construction of Interlocking Concrete Pavements for further guidance on construction practices.

Note: The elevations and surface tolerance of the base determine the final surface elevations of concrete paving slabs. The slab installation contractor cannot correct deficiencies in the base surface with additional bedding sand or by other means. Therefore, the surface elevations of the base should be checked and accepted by the General Contractor or designated party, with written certification to the paving subcontractor, prior to placing bedding sand and concrete paving slabs.

1. General Contractor shall inspect, accept and certify in writing to the slab installation subcontractor that site conditions meet specifications for the following items prior to installation of concrete paving slabs.
 - a. Verify that subgrade preparation, compacted density and elevations conform to specified requirements.
 - b. Verify that geotextiles, if applicable, have been placed according to drawings and specifications.
 - c. Verify that [Aggregate] [Cement-treated] [Asphalt-treated] [Concrete] [Asphalt] base materials, thickness, [compacted density], surface tolerances and elevations conform to specified requirements.
 - d. Provide written density test results for soil subgrade, [aggregate] [cement-treated][asphalt-treated][asphalt] base materials to the Owner, General Contractor and paving slab installation subcontractor.
 - e. Verify location, type, and elevations of edge restraints, [concrete collars around] utility structures, and drainage inlets.
2. Do not proceed with installation of bedding sand and concrete paving slabs until [subgrade soil and] base conditions are corrected by the General Contractor or designated subcontractor.

3.03 PREPARATION

- A. Verify base is dry, certified by General Contractor as meeting material, installation and grade specifications.
- B. Verify that base [and geotextile] is ready to support sand, [edge restraints,] and, slabs and imposed loads.
- C. Edge Restraint Preparation:
 1. Install edge restraints per the drawings [and manufacturer's recommendations] [at the indicated elevations].

Note: Retain the following two subparagraphs if specifying edge restraints that are staked into the base with spikes.

2. Mount directly to finished base. Do not install on bedding sand.
3. The minimum distance from the outside edge of the base to the spikes shall be equal to the thickness of the base.

3.04 INSTALLATION

- A. Spread bedding sand evenly over the base course and screed to a nominal 1 in. (25 mm) thickness, not exceeding 1 1/2 in. (40 mm) thickness. Spread bedding sand evenly over the base course and screed rails, using the rails and/or edge restraints to produce a nominal 1 in. (25 mm) thickness, allowing for specified variation in the base surface.
 1. Do not disturb screeded sand.
 2. Screeded area shall not substantially exceed that which is covered by slabs in one day.
 3. Do not use bedding sand to fill depressions in the base surface.

Note: When initially placed on the bedding sand, manually installed slabs often touch each other, or their spacer bars if present. Joint widths and lines (bond lines) are straightened and aligned to specifications with rubber hammers and pry bars as paving proceeds.

- A. Lay slabs in pattern(s) shown on drawings. Place units hand tight without using hammers. Make horizontal adjustments to placement of laid slabs with rubber hammers as required.
- B. Provide joints with spacers on each stone. Fill all joints with polymeric sand
- C. Fill gaps at the edges of the paved area with cut slabs or edge units.
- D. Cut slabs to be placed along the edge with a [double blade slab splitter or] masonry saw. Cut units shall be no smaller than [1/3 of a whole slab].
- E. Keep skid steer and forklift equipment off newly laid slabs that have not received initial compaction and joint sand.
- F. After an area is completely paved, compact the units into the sand with a mechanical plate vibrator using rollers or a neoprene pad.
- G. Use a low-amplitude plate compactor (with protective membrane). Use a protective sheet (at least 4'x8') to disperse compaction. Remove any cracked or damaged slabs and replace with new units.
- H. Simultaneously spread, sweep and compact dry joint sand into joints continuously until full. This will require at least 4 to 6 passes with a plate compactor. Do not compact within 6 ft (2 m) of unrestrained edges of paving units.
- I. All work within 6 ft. (2 m) of the laying face must shall be left fully compacted with sand-filled joints at the end of each day or compacted upon acceptance of the work. Cover the laying face or any incomplete areas with plastic sheets overnight if not closed with cut and compacted slabs with joint sand to prevent exposed bedding sand from becoming saturated from rainfall.
- J. Do not exceed a grade change of 1" every 10' in any direction.
- K. Remove excess sand from surface when installation is complete.
- L. Surface shall be broom clean after removal of excess joint sand.

3.05 FIELD QUALITY CONTROL

Note: Surface tolerances on flat slopes should be measured with a rigid straightedge. Tolerances on complex contoured slopes should be measured with a flexible straightedge capable of conforming to the complex curves on the pavement surface.

Note: For installations on a compacted aggregate base and soil subgrade, the top surface of the slabs may be 1/8 to 1/4 in. (3 to 6 mm) above the final elevations after compaction. This helps compensate for possible minor settling normal to pavements.

- C. The surface elevation of slabs shall be 1/8 in. to 1/4 in. (3 to 6 mm) above adjacent drainage inlets, concrete collars or channels.
- D. Lippage: No greater than 1/4 in. difference in height between adjacent slabs.

Note: Cleaning and sealing may be required for some applications. See [ICPI Tech Spec 5](#), Cleaning and Sealing Interlocking Concrete Pavements for guidance on when to clean and seal the slab surfaces, and when to stabilize joint sand. Delete article below if cleaners, sealers, and or joint sand stabilizers are not applied.

3.06 JOINT SAND STABILIZATION]

- A. Apply joint sand stabilization materials or polymeric sand between concrete slabs in accordance with the [Rinox](#) recommendations.

3.07 PROTECTION

- A. After work in this section is complete, the General Contractor shall be responsible for protecting work from damage due to subsequent construction activity on the site.

END OF SECTION